

COLUMBIA CTH J (Lindsay Road to CTH CS)
PHASING DESCRIPTION FOR PROJECT WORK

County will be conducting a road surface level improvement on CTH J this summer. Work will run from Lindsay Road (at the south end) up to CTH CS (on the north end). Work includes; clearing and grubbing, ditching and drainage corrections, culvert replacement, minor off-roadway grading and slope corrections, guardrail replacement, full depth pavement removal, subsurface corrections, and installation of a new asphalt surface. Work will be conducted in several phases, as follows;

1. Public Meeting was held January 12, 2022.
2. Phase 1: February thru early May of 2022, along the entire roadway section: tree removals, vegetation clearing, minor utility relocations.
3. Phase 2A: April 11th thru the end of May.
 - a. Road Closed, Local Traffic ONLY. "Local Traffic" by statute means that the individual has a destination that lies within the area of the road closure barricades and signage.
 - b. CTH J will be closed from Lindsay Rd to Richards Rd intersection with CTH V.
 - c. CTH VJ will be closed from Richards Rd to CTH V (near the school forest).
 - d. Work is to include; full depth pavement removal, culvert extensions, ditching, subsurface re-grading, replacement of the asphalt surface, painting.
 - e. Work is weather sensitive and weather dependent.
4. Phase 2B: Richards Rd intersection with CTH V @ CTH J will remain open until around May 16.
 - a. On May 16th, Richards Rd intersection with CTH J will be closed until the end of May (project completion).
 - b. CTH J pavement thru the intersection is being replaced as well as a culvert under Richards Rd and minor ditching/site improvements near Richards Rd.
5. Phase 3: Beginning Monday, June 6th until mid or late July (upon completion of Phase 2A and 2B):
 - a. CTH J from CTH V (near school forest) to CTH CS will be closed with Local Traffic Only (local = has a destination within the road closed signage).
 - b. Work is to include; full depth pavement pulverization, right-of-way grading, road widening, shoulder grading, ditching, culvert installation, asphalt surface replacement, shouldering, painting, signage replacement.

Every effort is being made to minimize disruptions to traffic patterns and timing while still being able to complete the project in an efficient and cost-effective manner. The Department intends to have the project 100% complete by the end of July, depending on the weather. This work is being conducted by Columbia County with the assistance of Wisconsin Department of Transportation Local Road Improvement Program. Questions about this project or timing can be directed to Columbia County Highway & Transportation Department (608) 429-2156 or Highway@co.columbia.wi.us or check the Department webpage at [Columbia County Highway Home Page](#).

Chris Hardy, PE
Highway Commissioner

Columbia County Highway & Transportation Dept
P.O. Box 875
303 Old Highway 16 Rd West
Wycena, WI 53969
(608) 429-2136
(608) 697-4332

COLUMBIA CTH J RESURFACING PROJECT: PHASE SEGMENTS FOR WORK

